

~~XXXXXXXXXX~~

Enfield Community Center
Basketball Court

Exterior slab
4000 psi w/ air

50' x 30'

wire mesh
Power trowel finish

1500 sq ft

Labor:

Total → 7,350

prep / subgrade → 8 hr @ 175 → 1,400

form / place / finish 3\$ sq ft → 4,500

Soffcut floor 1\$ per linear ft → 110\$

mesh / chairs → 4 hr @ 175 → 700\$

Machine → 1 day \$300 2 hr strip / clean - 350

Materials:

400 Concrete - 20y w/ ~~stone~~ air 2% exterior → 2,700\$

Mesh - 50 pc @ 15\$ → 750\$

Chairs - 275\$

Line pump - 1,400\$

Stone

Total: 7,800

Total materials / Labor:

\$15,150 + 450

Labor - 7,350

mat. - 7,800 + Stone 15 tons → 450